

ADDENDUM NO. 2

DATE: January 21, 2021

PROJECT: **2021 Bridge Rehabilitation**

OWNER: VILLAGE OF GURNEE

TO: PROSPECTIVE BIDDERS

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents approved for bid, with the amendments as noted below.

This Addendum consists of two (2) pages. This Addendum contains the following revisions:

Clarifications:

1. On structure # 049-6162 on Cunningham Ct:
 - a. For the East Abutment, seal the joint in accordance with Section 1050.02 Hot-Poured Joint Sealer stated in the Standard Specifications.

Schedule of Prices:

1. On structure # 049-6162 on Cunningham Ct:
 - a. Remove Pay Item #5 "REPLACE RAILING". This pay item will not be used and will not count towards total Project Cost.

CHANGES TO THE CONTRACT DOCUMENTS AND SPECIFICATIONS

Project Manual

- Remove and replace the bid documents, SCHEDULE OF PRICES, in its entirety, with page 2 of this Addendum

Signed:  _____

Village of Gurnee
Nicholas Leach
Project Engineer

Please acknowledge receipt of this Addendum by signing below and faxing or emailing a copy of the Addendum to the Village of Gurnee, Engineering Department at (847)-623-9475 or engineering@village.gurnee.il.us. Failure to do may disqualify the Bidder.

Firm

By

Name

Title

2021 BRIDGE REHABILITATION
VILLAGE OF GURNEE
IMEG NO. 20005657.00
SCHEDULE OF PRICES

(For complete information covering these items, see plans and specifications.)

STRUCTURE NO. 049-6400					
LEONARD DRIVE OVER SPINNEY RUN CREEK					
Item No.	Item	Units	Quantity	Unit Price	Total
1	DECK SLAB REPAIR(PARTIAL)	SY	55		
2	CONCRETE PATCH	SY	0.5		
3	EPOXY CRACK INJECTION	FOOT	50		
4	REPLACE BOARD(1"X12"X12', CEDAR)	EACH	1		
5	TRAFFIC CONTROL AND PROTECTION	LS	1		
STRUCTURE 1 TOTAL					

STRUCTURE NO. 049-6401					
LEONARD DRIVE OVER SHERMER CORNERS CREEK					
Item No.	Item	Units	Quantity	Unit Price	Total
1	CONCRETE PATCH	SY	0.5		
2	REMOVE SEDIMENT FROM CELL	LS	1		
3	TRAFFIC CONTROL AND PROTECTION	LS	1		
STRUCTURE 2 TOTAL					

STRUCTURE NO. 049-6162					
CUNNINGHAM COURT OVER SHERMER CORNERS CREEK					
Item No.	Item	Units	Quantity	Unit Price	Total
1	BRIDGE DECK SCARIFICATION, 2.25"	SY	140		
2	BRIDGE DECK LATEX CONCRETE OVERLAY, 2.25"	SY	140		
3	NEOPRENE EXPANSION JOINT	FOOT	31		
4	JOINT SEAL	FOOT	31		
5	REPLACE RAILING	EACH	1	---	---
5 6	TRAFFIC CONTROL AND PROTECTION	LS	1		
STRUCTURE 3 TOTAL					

STRUCTURE 1, 2, & 3 TOTAL					
--------------------------------------	--	--	--	--	--